



NOTES:

1. TRACER WIRE SHALL BE TAPED AT 10-FOOT INTERVALS TO THE TOP OF ALL NON-METALLIC MAINS AND ON WATER SERVICE LINES UP TO WATER METER TILE.
2. VALVE BOX AND LID SHALL BE SET 1/4 INCH BELOW FINISH GRADE IN ASPHALT AREAS. SET VALVE BOX TO GRADE IN UNPAVED AREAS AND CENTER IN A CONCRETE PAD SLOPED IN DIRECTION OF TRAVEL WITH A MINIMUM DEPTH OF 6 INCHES AND A MINIMUM WIDTH OF 1 FOOT AROUND OUTSIDE OF VALVE BOX.
3. VALVE OPERATING NUT MORE THAN 4 FEET BELOW GRADE SHALL HAVE AN APPROVED EXTENSION INSTALLED TO BRING TOP OF OPERATING NUT TO 24 INCHES TO 36 INCHES BELOW FINISH GRADE.
4. ALL CONSTRUCTION AND MATERIALS SHALL MEET THE COMMUNITY STREET AND UTILITY STANDARDS 2009 AND BE APPROVED BY THE CITY OF EPHRATA.
5. VALVE BOXES SHALL COMPLY WITH THE EPHRATA COMMUNITY STREET AND UTILITY STANDARDS CHAPTER 9-30.3(4).

DATE	REVISION	BY
VALVE AND TRACER WIRE INSTALLATION		
EPHRATA PUBLIC WORKS DEPARTMENT		
CITY OF EPHRATA		
DRAWN		<div style="border: 1px solid black; width: 40px; height: 40px; margin: 0 auto;"></div>
CHECK		
SCALE	NTS	
DATE	10/03/08	
GRANT COUNTY		WASHINGTON

